

PRICE INFORMATION SCHEDULES

SCHEDULE 1: PRICE SUMMARY AND TERMS OF PAYMENT

Tenderers shall set out in this Schedule:

1. **Price Summary** including the breakdown of the overall Tender Price stated in the Tender Form and any other terms of payment. The breakdown shall be detailed in the following format according to the summary of items and quantities required in the Tender. The price shall include any labour charges, custom tax and with holding tax.
2. Payment will be made locally and in Brunei Dollars. Payment shall be made in accordance with the provisions in the Contract.

SCOPE OF WORK FOR REPAIRING & LAYING OF FIBER OPTIC CABLE BETWEEN RIMBA AND BUKIT AGOK					
Item	Description	Unit	Qty	Rate	Amount
A	DUCTING WORKS Repair blockage 1-way 100mm ducts with complete with green tape identification marker				
1	Duct Blockage Repair - Grass Surface Area (Max 2m/lot) repair ducting	Lot	500		
2	Duct Blockage Repair - Reinforced Concrete Area (Max 2m/lot) repair ducting	Lot	150		
3	Duct Blockage Repair - Asphalt Surface Area (Max 2m/lot) repair ducting	Lot	150		
Total					
B	NEW DUCTING WORKS (DUE TO UNKNOWN CONDITION) From From Bkt Agok to Rimba from MH177 to MH179 (MH 178 MISSING) & From MH181 to MH181/03	Unit	Qty	Rate	Amount
1	Supply & Install 1 x 100mm diameter PVC Class B pipe sleeve laid in underground grass 900mm with underground green warning tape	meter	6000		



2	Supply & Install 1 x 100mm diameter PVC Class B pipe on carriageway. Inclusive of cutting, hacking reinstatement of asphalt (Max depth 900mm)	meter ²	1000		
3	Supply & Install Telephone Manhole FJB4 complete with frame, cover & accessories with MINDEF Logo	each	6		
4	Lead in duct 1 way to existing joint box FJB4	each	6		
5	HDD For HDPE (Including Supply of HDPE Pipe) 100mm per meter	meter	60		
Total					
B	NEW DUCTING WORKS From Foothill of Bt. Agok To Bt. Agok Building (MH 092 To New MH092-12)	Unit	Qty	Rate	Amount
1	Supply & Install 1 x 100mm diameter PVC Class B pipe sleeve laid in underground grass 900mm with underground green warning tape	meter	2500		
2	Supply & Install 1 x 100mm diameter PVC Class B pipe on carriageway. Inclusive of cutting, hacking reinstatement of asphalt (Max depth 900mm)	meter ²	500		
3	Supply & Install Telephone Manhole FJB4 complete with frame, cover & accessories with MINDEF Logo	each	12		
4	Lead in duct 1 way to existing joint box FJB4	each	4		
5	HDD For HDPE (Including Supply of HDPE Pipe) 100mm per meter	meter	15		
Total					



C	EXISTING FJB4 - MINDEF TELEPHONE MANHOLE	Unit	Qty	Rate	Amount
1	Plastering (Both Manhole & Cover)	each	10		
2	Supply & Install Manhole Cover FJB4 with MINDEF logo	each	2		
Total					
D	CABLE WORKS	Unit	Qty	Rate	Amount
1	Rod & Rope 100mm existing duct	meter	25000		
2	Laying 48 core Single Mode Fiber Cable (ITU. G655) Mindef Supply G655 Fiber Cable	meter	4500		
3	Supply & Laying 24 core Single Mode Fiber Cable (ITU. G655) from Rimba to Bkt Agok	meter	22000		
4	Supply & Laying 24 core Single Mode Fiber Cable (ITU. G652) Penanjong Exchange – CLS building 2nd floor	meter	1500		
5	Supply & Install Joint Closure 3M Type max 48 core	each	12		
6	Splicing 48 core at Manhole	each	12		
7	Supply & Install 48core Rack Mounted G655 SC connector & Adapter	each	4		
8	Supply & Install 24core Rack Mounted G652 SC connector & Adapter	each	4		
9	Termination at ODF 48core	each	4		
10	Termination at ODF 24core	each	4		
Total					



E	DESCRIPTION	Unit	Qty	Rate	Amount
1	Comms Test using OTDR 48core (both side)	Lot	1		
2	Test result document				
3	Single Line fiber Connection Diagram				
4	Google Earth (.kmz file)				
Total					
Grand Total					

NOTE:

- The Government reserves the right to give PARTIAL AWARD.
- The Government may accept the whole or any item(s) of tender.
- The Price quotes need to be maintained in items of partial award.
- **SPECIFICATIONS AND CATALOGUE MUST BE SUBMITTED AND CLEARLY LABELED.**

