

KETERANGAN PEMBELIAN TEMPATAN - JKP KEMENTAH

LAMPIRAN 'A'

RUJUKAN SEBUTHARGA : MINDEF / DFA / FY2026 / ITAU / DITU / LP / 033

TARIKH TUTUP SEBUTHARGA : 5 / 11 / 2026 (KHAMIS, 08:00 PAGI)

PETI PENERIMAAN SEBUTHARGA : BOX (01)

ALAMAT BARU: : ARAS BAWAH, BANGUNAN ARKIB
KEMENTERIAN PERTAHANAN, BOLKIAH GARISSON

NAMA SYARIKAT : _____

COP SYARIKAT & TANDATANGAN : _____

TEL PEMBEKAL : _____ FAX PEMBEKAL : _____

EMAIL PEMBEKAL : _____

TAFIS VENDOR ID : _____

BIL	KETERANGAN BARANG	KTI	HARGA SATU	HARGA SEMUA	TEMPOH SAH HARGA (MINIMUM 180 HARI)	TEMPOH PENGHANTARAN	BUATAN NEGERI	LAIN-LAIN HAL
1	<u>PEMINDAHAN PERALATAN DAN KABEL RANGKAIAN BAGI PEJABAT MUZIUM ANGKATAN BERSENJATA DIRAJA BRUNEI (ABDB)</u> Pemindahan Peralatan dan Kabel Rangkaian Note: Please contact PW2 Noorizul at +673 7370373, for further inquiries Note: Sila rujuk spesifikasi yang disertakan (Annex 'A') <u>PERHATIAN:</u> Perkara-perkara yang perlu (mandatori) dihadapkan sebelum tarikh tutup sebutharga: ☐ / Katalog (Spesifikasi penuh) ☐ / Authorization Letter * Katalog yang dihadapkan hendaklah menggunakan katalog bagi item yang ditawarkan dan bukan menggunakan katalog yang disertakan Jabatan ini. Jika didapati gagal, sebutharga tersebut tidak akan dipertimbangkan.	1 LOT						

JUMLAH SEMUA HARGA YANG DITAWARKAN - ANGKA B\$ _____ DAN PERKATAAN : _____

9/10

KETERANGAN/SKOP KERJA YANG DIPOHONKAN

Bil	Keterangan/Skop Kerja	Jumlah	Harga Seunit	Harga Semua
1	Supply, delivery, installation, configuration, testing and commissioning of single mode fiber optic network infrastructure for Pejabat Muzium ABDB, Bolkiah Garison, with the following scope of work: a) Splicing of 12-core single-mode fiber optic cable with SC/UPC termination. b) Supply and install 1U rackmount Fiber Optic Patch Panel 12-core ODF with SC/UPC connectors. c) Supply and install of fiber optic splice closure for fiber cable extension from existing manhole to new location within the building. d) Supply and install G.652 single-mode fiber optic cable for extension from existing manhole to the new switch rack location within the building. e) Supply, install, test and commissioning of Cat6 Network LAN points within the building.	01 Lot 09 units 01 unit 100 mtr 12 points		
2	Rack and Cable Migration Works: a) Disconnect and dismantle the existing ODF, switches, patch panels and cables from the existing rack/location, and relocate and reinstall them at the new designated location. b) Re-termination of existing cables as required. c) Jointing and extension of any cables that are insufficient in length, using suitable cable jointing and termination modules, including all necessary accessories.	01 Lot		
3	Cabling Works: a) Labelling of fiber optic patch panel and patch cord. b) Tidy all previous network cables and fiber by using casing, conduits or trunking. c) Removal and disposal of unused LAN cables and fiber optic cables within the building. d) Close any holes into fiber optic panel to protect from pests.	01 Lot		
4	Tenderers are required to attach: a) FTTH Certificate for Fiber Optic Splicing and Management (Main Contractor or Sub Contractor). b) Catalogue and technical specification.	-	-	-
JUMLAH HARGA KESELURUHAN				

